



#### CONSTRUCTION:


Door frames are constructed using 1-3/8" thick finger-jointed West Coast Hem/Fir with Mortise and Tenon stiles and rails. Solid Rails are an available option and recommended if the door is to be stained. Doors faces are sanded and ready for field finishing by others. (All wood doors should be finished and protected from the weather prior to the door's installation)

Raised panels are 3/4" thick; choose from Hem/Fir Panels, Clear Cedar Panels, or Redwood Panels. Also available, the "All Cedar Raised Panel Door" manufactured with a solid Western Red Cedar Frame and Clear Western Red Cedar Panels.

Recessed panel are 1/4" panel thick; choose from Luan Mahogany Plywood, Rough Sawn Fir Plywood, and Tempered One Side Hardboard Panels.

Flush door back, insulate door and laminated reinforced raised panels are optional and can be specified at time of purchase.

### **WINDOW DESIGNS:**




# STANDARD SIZES, PANEL & SECTION ARRANGEMENTS:

STANDARD WIDTHS:	8'-0"	9'-0"	10'-0"	12'-0"	16'-0"	18'-0"
Panels Horizontally	2,3,4	2,3,4	3,4	3,4,6	4,5,8	5,8

STANDARD HEIGHTS:	7'-0"	8'-0"	9'-0"	10'-0"	12'-0"	14'-0"
Recessed Panels Vertically	4,5	5	5	5	6	7
Raised Panels Vertically	5	6	7	8	9	11

#### **EXAMPLES OF PANEL ARRANGEMENTS, 5 SECTION RAISED PANEL DOORS SHOWN**



# **WARRANTY:**

5 Section, 8 Panel

All wood garage doors manufactured by Northwest Door, Inc are warrantied against defects in material and/or workmanship for a period of one year from date of purchase to the original purchaser. Upon inspection, Northwest door will supply, only the defective parts to the original purchaser. Northwest door agrees to repair or replace at no charge any part, parts, or complete unit found to be defective by Northwest Door within this period. Northwest Door will not be responsible for painting, shipping, labor, transportation and/or field charges. Customer Responsibility: To validate this warranty, the doors must not be allowed to get wet prior the application of protective finish to the door. The door must be finished with one (1) prime coat of exterior oil based primer and two (2) coats of finish exterior paint applied to surfaces and edges prior to or immediately after installation.

5 Section, 10 Panel

Northwest, Door, Inc. - Po Box 44605 - Tacoma, WA 98444 - www.nwdusa.com



5 Section, 12 Panel